



KIRLOSKAR CHILLERS PRIVATE LIMITED

A Kirloskar Group Company

Enriching Lives

Document No : ESP-16-17-105				
Document Name: Compressor, Oil pump Pressure Testing Guidelines				
Prepared By: AFK	Checked By: SNM	Approved By: SSN	Date : 03/07/2017	No of pages. : 02

Engineering Specification

Compressor, Oil pump Pressure Testing Guidelines

Revision No.	Date :	Description	Prepared By :	Appd. By :
R00	03/07/2017	Initial release	AFK	SSN



KIRLOSKAR CHILLERS PRIVATE LIMITED

A Kirloskar Group Company

Enriching Lives

Centrifugal Compressor, Oil pump:

Equipment	Test pressure (pneumatic)
All compressor assembly CE (MD) certified & Non-CE	16 kgf/cm ²
Oil sump assembly CE certified (MD)	20.5 kgf/cm ²
Oil sump assembly Not certified	16 kgf/cm ²
Repaired compressor & oil pump leak test	14 kgf/cm ²

- Individual Volute & discharge nozzle shall be pressure tested at 20.5 kgf/cm². Scrap used hardware immediately after testing of each volute. Same information shall be available on individual drawings.
- Other casting components can be pressure tested at max. 16 kgf/cm² for porosity & blow holes checking.
- 12.9 Grade hardware only shall be used for pressure testing.
- Re- torque shall be applied as per released chart after each pressure testing.
- No separate leak test required for new compressor & oil pump.

Screw Compressor:

Equipment	Test pressure (pneumatic)
CXH/KXH/KXI used for R134a refrigerant application	23 kgf/cm ²
CXH used for R407C/R22 refrigerant application	30 kgf/cm ²
Frame4/Frame3/Melco used for R134a refrigerant application	23 kgf/cm ²
Frame4/Frame3/Melco used for R407C/R22 refrigerant application	30 kgf/cm ²

- Above pressures are applicable for leak testing of **repaired compressors** only. No strength test shall be performed.
- Before pressure testing always confirm type of refrigerant used and refer corresponding pressure value from above table for testing.
- Re- torque shall be applied as per released chart after each pressure testing.