

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document No : ESP-22-23-003				
Document Name : VFD Retrofit cable schedule (55-160KW)				
Prep. By : IGP	Checked By : IGP	Appd. By :ASP	Date : 10/05/22	Total Pages : 01

Table-1 : Power cable			
VFD (KW)	Current (A)	Cable Sq. mm.	VFD Side Lug
55	106	50	Pin type
75	147	70	Pin type
90	177	70	Pin type
110	212	95	Ring type ID10
132	260	120	Ring type ID10
160	315	150	Ring type ID10

Table-2 : Control cable	
For commands	10C X 1.0 SQ.MM Copper flexible cable
For speed control signal	2C X 1 SQ.MM, Copper Shielded cable

NOTE :

1. For any Special/Nonstandard requirement, consult with engineering
2. For prewired chiller mounted panel, refer table 1 only
3. In case of separate starter panel, refer table 1 for power cables & table 2 for interfacing cables