

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller		
Document No : ESP-25-26-001	Revision : R00	Date : 15/03/2025
Prepared By : AKC	Approved By : SKP	Sheet : 1 of 11

CONTROL SETPOINTS



CONTROL SETPOINT

29/08/24 Thu 21:52:32
FACTORY

CONTROL
CURRENT
TEMPERATURE
PRESSURE
COMPRESSOR
TIMERS
CONFIGURATION
EXV OIL T
EXV

SETPOINT	°C
CONTROL BAND	°C
DEAD BAND	°C
COMPRESSOR ON DELTA-T	°C
LWT SP MIN	°C
LWT SP MAX	°C

MBFV Operating Temp SP	°C
Control Band	°C
Buffer Delay	SEC

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

CONTROL SETPOINT						
PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
SETPOINT	°C		AS PER USER		10	20
CONTROL BAND	°C		4		0	99
DEAD BAND	°C		0.4		0	99
COMP ON DELTA-T	°C		0			
LWT SP MIN	°C		14		5	16
LWT SP MAX	°C		20		15	20
MBFV OPERATING TEMP SP	°C		AS PER USER		5	30
CONTROL BAND	°C		3		0	20
BUFFER DELAY	SEC		30		0	99

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller

Document No : ESP-25-26-001

Revision : R00

Date : 15/03/2025

Prepared By : AKC

Approved By : SKP

Sheet : 2 of 11

CURRENT SETPOINTS



AS
ACTUAL

CURRENT DATE
DD / MM / YY
29 8 24

CURRENT TIME
14 55

CURRENT SETPOINT

29/08/24 Thu 21:52:37
FACTORY

FULL LOAD POWER	
COMP 1	COMP 2
LOW CURRENT TRIP SP	%
INITIAL BYPASS TIME	SEC
ALARM DELAY WHILE RUNNING	SEC
HIGH CURRENT TRIP SP	%
INITIAL BYPASS TIME	SEC
ALARM DELAY WHILE RUNNING	SEC
HIGH CURRENT UNLOAD	%
HIGH CURRENT RELOAD	%
HIGH CURRENT UNLOAD HOLD	%
HIGH CURRENT LOAD HOLD	%
DEL COMP SAFETY HOLD	SEC

CONTROL

CURRENT

TEMPERATURE

PRESSURE

COMPRESSOR

TIMERS

CONFIGURATION

EXV OIL T

EXV

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

CURRENT SETPOINT						
FULL LOAD POWER	COMP-1	REFER TDS		COMP-2	REFER TDS	
PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
LOW CURRENT TRIP SP	%	20	20		0	30
INITIAL BYPASS TIME	SEC	5	10		0	50
ALRM DELAY WHILE RUNNING	SEC	2	2		0	30
HIGH CURRENT TRIP SP	%	120	112		101	120
INITIAL BYPASS TIME	SEC	4	5		0	50
ALRM DELAY WHILE RUNNING	SEC	2	2		0	30
HIGH CURRENT UNLOAD	%	101	101		90	110
HIGH CURRENT RELOAD	%	96	95		70	100
HIGH CURRENT UNLOAD HOLD	%	100	97		70	105
HIGH CURRENT LOAD HOLD	%	98	96		70	105
DEL COMP SAFETY HOLD	SEC	30	10		0	50

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller

Document No : ESP-25-26-001

Revision : R00

Date : 15/03/2025

Prepared By : AKC

Approved By : SKP

Sheet : 3 of 11

TEMPERATURE SETPOINTS



TEMPERATURE SETPOINT

29/08/24 Thu 21:52:40
FACTORY

OIL HEATER SETTINGS

ON SP

OFF SP

DELTA T

ANTI-FREEZE TRIP SP °C

HIGH OIL TEMP TRIP SP °C

HIGH OIL TEMP UNLOAD °C

HIGH OIL TEMP HOLD °C

HIGH OIL TEMP RELOAD °C

HIGH DISCH TEMP TRIP SP °C

HIGH DISC TEMP UNLOAD °C

HIGH DISCH TEMP HOLD °C

HIGH DISCH TEMP RELOAD °C

OIL LEVEL SW DELAY

INITIAL BYP DELAY 300SEC

RUNNING DELAY 60 SEC

ALARM DELAY

5 SEC

1 SEC

1 SEC

CONTROL

CURRENT

TEMPERATURE

PRESSURE

COMPRESSOR

TIMERS

CONFIGURATION

EXV OIL T

EXV

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

TEMPERATURE SETPOINT						
	UOM	PROGRAM DEFAULT	ENGG SET	FACTORY SET	MIN	MAX
ANTI-FREEZE TRIP SP	°C	4.4	5		3	20
ANTI-FREEZE TRIP ALRM DELY	SEC	5	5			
HIGH OIL TEMP TRIP SP	°C	80	80		30	95
HIGH OIL TEMP TRIP ALRM DELY	SEC	1	1			
HIGH OIL TEMP UNLOAD	°C	5	3		0	10
HIGH OIL TEMP HOLD	°C	5	5		0	10
HIGH OIL TEMP RELOAD	°C	7	7		0	15
HIGH DISC TEMP TRIP SP	°C	75	80		40	90
HIGH DISC TEMP TRIP ALRM DELY	SEC	1	1			
HIGH DISC TEMP UNLOAD	°C	3	3		0	10
HIGH DISC TEMP HOLD	°C	5	5		0	10
HIGH DISC TEMP RELOAD	°C	7	7		0	15
OIL HEATER ON SP	°C	20	10		5	25
OIL HEATER OFF SP	°C	10	10		5	25
OIL DELTA T	°C	10	20		5	25
OIL LEVEL INITIAL BYP DELAY	SEC	300	300		0	400
RUNNING DELAY	SEC	60	60		0	100

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller

Document No : ESP-25-26-001

Revision : R00

Date : 15/03/2025

Prepared By : AKC

Approved By : SKP

Sheet : 4 of 11

PRESSURE SETPOINTS

Kirloskar Chillers

PRESSURE SETPOINT 29/08/24 Thu 21:52:44 FACTORY

LOW DISC PRESSURE TRIP	BAR	HIGH DISC PRESSURE TRIP SP	BAR
INITIAL BYPASS TIME	SEC	HIGH DISC PRESSURE UNLOAD	BAR
UNSAFE OIL PRESSURE TRIP	BAR	HIGH DISC PRESSURE HOLD	BAR
INITIAL BYPASS TIME	SEC	HIGH DISC PRESSURE RELOAD	BAR
DIRTY FILTER PRESSURE TRIP	BAR	LOW SUC PRESSURE TRIP SP	BAR
INITIAL BYPASS TIME	SEC	INITIAL BYPASS TIME	SEC
RUNNING DELAY	SEC	AL DELAY WHILE RUNNING	SEC
NO OIL FLOW TRIP	BAR	LOW SUC PRESSURE UNLOAD	BAR
INITIAL BYPASS TIME	SEC	LOW SUC PRESSURE HOLD	BAR
RUNNING DELAY	SEC	LOW SUC PRESSURE RELOAD	BAR
		VERY LOW SUC PRESSURE TRIP SP	BAR
		LOW OIL DIFFERENTIAL TRIP SP	BAR
		INITIAL BYPASS TIME	SEC

STATUS COMP 1 : OFF BY SWITCH STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW ALARM HISTORY ATS STATUS ALARM REALTIME ALARM LOG USER SETPOINT SUPV SETPOINT

PRSSURE SETPOINT						
PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
HIGH DISC PR TRIP SP	BAR	21	19		4.5	25
HIGH DISC PR UNLOAD	BAR	1	0.7		0	6
HIGH DISC PR HOLD	BAR	1.5	1		0	9.9
HIGH DISC PR RELOAD	BAR	2	1.3		0	9.9
LOW SUC PR TRIP SP	BAR	1.7	1.7		1.3	3
INITIAL BYP TIME	SEC	30	30		0	90
ALRM DELAY WHILE RUNNING	SEC	15	15		0	60
LOW SUC PR UNLOAD	BAR	0.1	0.2		0	1
LOW SUC PR HOLD	BAR	0.2	0.3		0	1
LOW SUC PR RELOAD	BAR	0.3	0.1		0	1
VERY LOW SUC PR TRIP SP	BAR	1.5	1.5		1	3
LOW OIL DIFF TRIP SP	BAR	2.5	2.5		1.5	9
INITIAL BYP TIME	SEC	300	300		0	400
LOW DISC PR TRIP	BAR	4.5	4.5		1.5	9.9
INITIAL BYP TIME	SEC	15	7		0	120
UNSAFE OIL PR TRIP	BAR	1.8	1.8		1	5
INITIAL BYP TIME	SEC	30	30		0	120
DIRTY FILTER PR TRIP	BAR	3	3		1.5	5
INITIAL BYP TIME	SEC	60	60		0	120
RUNNING DELAY	SEC	60	60		0	60
NO OIL FLOW TRIP	BAR	3	2.5		1.5	5
INITIAL BYP TIME	SEC	30	30		0	60
RUNNING DELAY	SEC	5	5		0	30

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller		
Document No : ESP-25-26-001	Revision : R00	Date : 15/03/2025
Prepared By : AKC	Approved By : SKP	Sheet : 5 of 11

COMPRESSOR SETPOINTS



SP COMP LOADING
LOAD UNLOAD BAND
STARTUP LOAD %

COMPRESSOR SETPOINTS

29/08/24 Thu 21:52:47
FACTORY

TIMING SP FOR COMPRESSOR	
MIN TIME BETWEEN STOP-START	SEC
MIN TIME BETWEEN START-START	SEC
FAST UNLOAD STARTUP TIME	SEC
FAST UNLOAD CUTOFF TIME	SEC
SAFETY HOLD TIME	SEC
STARTER DELAY	SEC
OIL FEED PRE START	SEC
OIL FEED POST STOP	SEC
PULSE PERIOD I	
PULSE PERIOD D	
	MINIMUM MAXIMUM
INCREMENT PULSE	mSEC
DECREMENT PULSE	mSEC
SAFETY UNLOAD HOLD	mSEC

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

COMPRSSOR SETPOINT						
PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
MIN TIME BETN STOP-START	SEC	180	30		0	500
MIN TIME BETN START-START	SEC	600	60		0	900
FAST UNLOAD STARTUP TIME	SEC	10	30		0	60
FAST UNLOAD CUTOFF TIME	SEC	30	30		0	60
SAFETY HOLD TIME	SEC	30	10		0	60
STARTER DELAY	SEC	3	3		0	30
OIL FEED PRE START	SEC	10	3		0	20
OIL FEED POST STOP	SEC	100	3		0	100
PULSE PERIOD I	mSEC	4	4		0	30
PULSE PERIOD D	mSEC	2	3		0	30
SP COMP LOADING	%	90	75		0	100
LOAD UNLOAD BAND	%	4	3		0	10
STARTUP LOAD	%	50	50		50	100
INCREMENT PULSE (MIN)	mSEC	500	25		0	2000
INCREMENT PULSE (MAX)	mSEC	900	100		0	2000
DECREMENT PULSE(MIN)	mSEC	50	50		0	2000
DECREMENT PULSE(MAX)	mSEC	350	200		100	5000
SAFETY UNLOAD HOLD (MAX)	mSEC	200	200		0	1500

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller		
Document No : ESP-25-26-001	Revision : R00	Date : 15/03/2025
Prepared By : AKC	Approved By : SKP	Sheet : 6 of 11

TIMER SETPOINTS



TIMER SETPOINT

29/08/24 Thu 21:52:50

FACTORY

CONTROL

CURRENT

TEMPERATURE

PRESSURE

COMPRESSOR

TIMERS

CONFIGURATION

EXV OIL T

EXV

EVAP FLOW SW DELAY

SEC

VOLTAGE PD DELAY

SEC

EXT EMERGENCY DELAY

SEC

WINDING PROTECTION DEL

SEC

TRANSITION ALARM DEL

SEC

DELAY SLAVE ON

SEC

SWITCH TIME FROM SOURCE 2

SEC

SWITCH TIME FROM SOURCE 1

SEC

EVAP PUMP ON DEL

SEC

EVAP PUMP OFF DEL

SEC

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

TIMER SETPOINT						
PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
EVAP FLOW SW DELAY	SEC	1	2		0	50
VOLTAGE PD DELAY	SEC	1	3		0	10
EXT EMERGENCY DELAY	SEC	4	2		0	10
WINDING PROTECTION DEL	SEC	10	3		0	10
TRANSITION ALRM DELAY	SEC	10	10		0	30
DELAY SLAVE ON	SEC	25	25		0	30
SWITCH TIME FROM SOURCE 2	SEC	1800	AS PER USER		0	999
SWITCH TIME FROM SOURCE 1	SEC	60	AS PER USER		0	999
EVAP PUMP ON DELAY	SEC	0	1		0	30
EVAP PUMP OFF DELAY	SEC	180	300		0	600

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller		
Document No : ESP-25-26-001	Revision : R00	Date : 15/03/2025
Prepared By : AKC	Approved By : SKP	Sheet : 7 of 11

CONFIG SETPOINTS



29/08/24 Thu 21:52:55
FACTORY

NO OF FANS PER CIRCUIT
18

ON DELAY

OFF DELAY

COND FAN PID SP

COND FAN PID DB

PID GAIN

PID INT

PID DER

HIGH LIMIT PID

LOW LIMIT PID

ANTIBUMP
NO YES

PID OUT MIN FOR FAN OFF
25.0 %

FAN MAN OPERATION
MAN CMD 0

AUTO MANUAL

CONTROL

CURRENT

TEMPERATURE

PRESSURE

COMPRESSOR

TIMERS

CONFIGURATION

EXV OIL T

EXV

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

CONFIG SETPOINT						
PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
NO OF FANS PER CKT	NUM	9	AS ACTUAL		0	20
ON DELAY	SEC	3	2		0	60
OFF DELAY	SEC	3	10		0	60
COND FAN PID SP	BAR	8	7		0	20
COND FAN PID DB	BAR	0.2	0.2		0	99.9
PID GAIN	-	0.4	0.4		0	99.9
PID INT	-	1	5		0	60
PID DER	-	10	10		0	60
HIGH LIMIT PID	%	72	90		0	100
LOW LIMIT PID	%	20	50		0	99.9
PID OUT MIN FOR FAN OFF	%	25	27		0	99.9
ANTIBUMP	-	NO	YES		-	-
FAN MANUAL OPERATION	-	AUTO	AUTO		-	-

Note:- CONFIG SETPOINTS values will change as per requirement.

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller		
Document No : ESP-25-26-001	Revision : R00	Date : 15/03/2025
Prepared By : AKC	Approved By : SKP	Sheet : 8 of 11

CONFIG SETPOINTS

ADDRESS

1

PROTOCOL

MODBUS

BAUDRATE

19200

NO

YES

CAPACITY CONTROL

EXV

NO

YES

VFD REF OVER MODBUS

NO

YES

VFD

NO

YES

STARTER-TYPE

START DELTA

SOFT STARTER

TR DISPLAY

NO

YES

	H	L	H	L
PRV. RUNHOURS	0	6	0	8
PRV. No. OF STARTS	0	8	0	6
RUNHOURS (NON-RESET)	0	6	0	8
SET MAINTAINANCE ALARM	8	0		

CONTROL

CURRENT

TEMPERATURE

PRESSURE

COMPRESSOR

TIMERS

CONFIGURATION

EXV OIL T

EXV

NOTE:- WHILE SETTING RUNHOURS, NO.OF START & MAINTAINANCE ALARM SEPARATE THE NUMBER IN TWO AS HIGH & LOW REFER THE EXAMPLE.. TO SET 5000 MAINTAINACE ALARM SEPARATE 5000 AS H - 5 & L -000. IF PREV RUNHOURS IS 39568 THEN SEPARATE 39568 AS H - 39 & L - 568

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

ANTIBUMP	YES	NO	ADDRESS	1	RANGE	0 To 247												
FAN MAN OPERATION	AUTO	MANUAL	<table><tr><td>PROTOCOL</td><td>BAUDRATE</td></tr><tr><td>CAREL</td><td>1200</td></tr><tr><td>MODBUS</td><td>2400</td></tr><tr><td>PCO WEB</td><td>4800</td></tr><tr><td>MODBUS EXTENDED</td><td>9600</td></tr><tr><td></td><td>19200</td></tr></table>				PROTOCOL	BAUDRATE	CAREL	1200	MODBUS	2400	PCO WEB	4800	MODBUS EXTENDED	9600		19200
PROTOCOL	BAUDRATE																	
CAREL	1200																	
MODBUS	2400																	
PCO WEB	4800																	
MODBUS EXTENDED	9600																	
	19200																	
EXV	YES	NO																
VFD REF OVER MODBUS	YES	NO																
VFD	YES	NO																
STARTER TYPE	STAR DELTA	SOFT STARTER																
TR DISPLAY	YES	NO																
CAPACITY CONTROL	YES	NO																
COMP	*H	*L	SET READY TIMER FOR QUICK START		5	RANGE												
PRV. RUNHOURS	0	0				0 To 30												
PRV. NO. OF STARTS	0	0																
RUNHOURS (NON RESET)	0	0																
SET MAINTAINANCE ALRM	0	0																

Note: - 1. CONFIG SETPOINTS can vary as per customized requirement.

2. Compressor Run Hours value need to updated in controller when installing a new compressor at customer site or uploading a new program in controller or Replacing old PLC controller with a new.

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller		
Document No : ESP-25-26-001	Revision : R00	Date : 15/03/2025
Prepared By : AKC	Approved By : SKP	Sheet : 9 of 11

EXV SETPOINTS FOR FEED OIL TEMP CONTROL



AUTO

MANUAL

AUTO

MANUAL

% MANUAL COMMAND

70.0

70.0

OIL COOLER EXV % OUTPUT

0.0

0.0

CONTROL SETPOINT

OIL TEMP DEAD ZONE

CONTROL PULSE

EXV OUT MAX %

EXV PULSE PERIOD

29/08/24 Thu 21:53:10

FACTORY

CONTROL

CURRENT

TEMPERATURE

PRESSURE

COMPRESSOR

TIMERS

CONFIGURATION

EXV OIL T

EXV

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

EXV SP FOR FEED OIL T CONTROL						
PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
CONTROL SETPOINT	°C	55	55		20	70
OIL TEMP DEAD ZONE	°C	5	5		0	30
CONTROL PULSE	STEP	10	3		0	50
EXV OUT MAX %	%	100	95		0	100
EXV PULSE PERIOD	SEC	6	5		0	15
EXV CONTROL – AUTO/MANUAL						
% MANUAL COMMAND	%	0	0		0	100

*EXV Control is to be kept in AUTO mode only, but when it switched MANUAL mode for troubleshooting then only need to enter the required % Manual command value.

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller

Document No : ESP-25-26-001

Revision : R00

Date : 15/03/2025

Prepared By : AKC

Approved By : SKP

Sheet : 10 of 11

EXPANSION VALVE SETPOINTS



SUCTION PR3.5

SUCTION SH1.0

DIFF PR.2.8

-VE BAND0.2

0.5

1.5

+VE BAND

0.5

PULSE MIN25

2

20

PULSE MAX40

4

45

EXV SETPOINTS

29/08/24 Thu 21:53:14

FACTORY

CONTROL

CURRENT

TEMPERATURE

PRESSURE

COMPRESSOR

TIMERS

CONFIGURATION

EXV OIL T

EXV

DELAY COMP-EXV

EXV PULSE PERIOD SP

EXV START OPRTN

EXV PULSE PERIOD SSH

EXV MIN. OPENING

EXV MAX. OPENING

EXV START OPENING

EXV Off Delay After Comp Off

AUTO

MANUAL

MANUAL COMMAND

EXV OUTPUT

15.5

0.0

STATUS COMP 1 : OFF BY SWITCH

STATUS COMP 2 : OFF BY SWITCH

CHILLER OVERVIEW

ALARM HISTORY

ATS STATUS

ALARM REALTIME

ALARM LOG

USER SETPOINT

SUPV SETPOINT

EXV SETPOINTS						
PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
DELAY COMP-EXV	SEC	30	20		0	99
EXV START OPRTN	SEC	20	20		0	100
EXV MIN OPENING	%	15	15		0	100
EXV PULSE PERIOD SP	SEC	20	20		0	20
EXV PULSE PERIOD SSH	SEC	15	7		0	30
EXV MAX OPENING	%	50	100		0	100
EXV START OPENING	SEC	45	35		0	100
EXV OFF DELAY AFTER COMP OFF	SEC	20	10		0	100
	SUCT PR	RANGE	SUCT SH	RANGE	DIFF PR	RANGE
SETPOINT	2.5	0 To 6	0.5	0 TO 5	2.8	0 To 5
NEGATIVE BAND	0.2	0 To 2	0.5	0 To 2	1.5	0 To 3
POSITIVE BAND			0.5	0 To 2		
PULSE MIN	25	0 To 30	2	0 To 15	20	0 To 30
PULSE MAX	40	0 To 60	3	0 To 20	45	0 To 60

Kirloskar Chillers Private Limited

A Kirloskar Group Company

Document Name : Instrument Set Point List For Air cooled Data centre chiller

Document No : ESP-25-26-001

Revision : R00

Date : 15/03/2025

Prepared By : AKC

Approved By : SKP

Sheet : 11 of 11

PROBE OFFSET SETPOINTS

Kirloskar Chillers

PROBE OFFSET SETPOINT 29/08/24 Thu 21:53:47 FACTORY

RANGE SELECTION

SUCTION PR. BAR
DISCH. PR. BAR BAR
OIL PR. BAR BAR

CT SELECTION
SELECT CT Manual Feed

WT HT
SELECT DISCHARGE PROBE TYPE

PROBE OFFSET FOR

SUCTION PR. BAR
SUCTION TEMP °C
DISCH PRESSURE BAR
DISCH TEMP °C
EVAP IN TEMP °C
EVAP OUT TEMP °C
AMB. TEMP °C
OIL PRESSURE BAR
OIL SUMP TEMP °C
COMP CURRENT AMP
LIQUID TEMP °C

CONTROL
CURRENT
TEMPERATURE
PRESSURE
COMPRESSOR
TIMERS
PROBES
CONFIGURATION
EXV OIL T
EXV

FLOW METER MAX RANGE
EVAP MAX LPM LPM
MANUAL CT AMP
FAN STATUS

STATUS COMP 1 : OFF BY SWITCH **STATUS COMP 2 : OFF BY SWITCH**

CHILLER OVERVIEW **ALARM HISTORY** **ATS STATUS** **ALARM REALTIME** **ALARM LOG** **USER SETPOINT** **SUPV SETPOINT**

PROBE OFFSET SETPOINTS

PARAMETERS	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
SUCTION PR	BAR	0	0		-99	99
SUCTION TEMP	°C	0	0		-99	99
DISCH PR	BAR	0	0		-99	99
DISCH TEMP	°C	0	0		-99	99
EVAP IN TEMP	°C	0	0		-99	99
EVAP OUT TEMP	°C	0	0		-99	99
EVAP OUT TEMP	°C	0	0		-99	99
AMB TEMP	°C	0	0		-99	99
OIL PR	BAR	0	0		-99	99
OIL SUMP TEMP	°C	0	0		-99	99
COMP CURRENT	AMP	0	0		-99	99
LIQUID TEMP	°C	0	0		-99	99

RANGE SELECTION	UOM	PROGRAM DEFAULT	ENGG SPECIFIED	FACTORY TEST	MIN	MAX
SUCTION PR	BAR	10	10		-327	327
DISCH PR	BAR	44.8	44.8		-999	999
OIL PR	BAR	44.8	44.8		-999	999
EVAP MAX LPM	LPM	2837	8333		0	65535
MANUAL CT	AMP	-	AS CALIB		0	9999