



Enriching Lives

KIRLOSKAR CHILLERS PRIVATE LIMITED

A Kirloskar Group Company

QUALITY ASSURANCE PLAN : CHILLER UNIT ASSEMBLY.					Document No.: QAP / STD / 300, Rev.: 00					Page 1 of 2
Sr No	Item Description	CHECK			Acceptance Norms.	Format of record	Inspection By			Remarks
		Characteristics	Method	Extent			M	C	I	
1	Compressor Assembly									
1a	Compressor Assembly	Pressure Test	Certificate Review	100%	Manufacturer Specification	Manufacturer certificate.	R/P	R	R	
1b	Motor for compressor	Motor Insulation Test	Meager	100%	KCPL specification	Inspection Report	P	R	R	
2-A	Heat Exchanger Assembly (Evaporator for all chillers & Condenser for water cooled chiller models)									
2a	Pneu. Test: Ref. Side	Leakage/ Pr. drop	Visual	100%	No any leakage and/ or pressure drop	Insp. Report	P	R	R	
	Hydro Test: Water side	Leakage/ Pr. drop	Visual	100%		Insp. Report	P	R	R	
2-B	Condenser Coils (For air cooled chiller models)									
2a	Pressure testing	Leakage/ Pr. drop	Visual	100%	Drawing, Material specification.	Inspection Report	P	R	R	
3	Panel Inspection									
3a	Panel inspection	Visual, dimensions	Visual, Measurement	100%	KCPL drgs / specification	Insp. Report.	P	R	R	
		Component Layout					P	R	R	
		Wiring check					P	R	R	
4	Chiller Unit Assembly.									
4a	Pneumatic Pressure Test (Refrigerant side)	Leakage/ Pr. drop	Visual	100%	No any leakage and/ or pressure drop	Insp. Report	P	R	R	
4b	Performance testing	Performance	Run test.	As per remark	KCPL specification	Log sheet	P	R	R	Performance run test of chillers shall be carried out at design & 100% load codition
4c	Final Inspection	Finish Painting	Visual & DFT	100%	KCPL specification	Insp. Report	P	R	R	
		Insulation	Visual	100%						
		Name plate, labels	Visual	100%						



Enriching Lives

QUALITY ASSURANCE PLAN : CHILLER UNIT ASSEMBLY.	Document No.: QAP / STD / 300, Rev.: 00	Page 2 of 2
---	---	-------------

Legends used:

M	Manufacturer (KCPL or KCPL sub vendor)
C	Client
I	Inspection Agency or Consultant
P	Perform Activity should be performed & inspected.
H	Hold Authorized inspector's hold point. Can not proceed without clearance
R	Review Documents will be submitted to authorized inspector for review.
NA	Not Applicable

Abbreviations:

KCPL	Kirloskar Chillers Pvt. Ltd.
MTC	Material Test Certificate.

--	--

				Checked & Approved By		
				: DVD	5.4.14	
00	First Issue	05.04.14	DVD (QA)	QA Plan Prepared By :		
REV	REVISION DESCRIPTION	DATE	APPROVED BY	RVH	5.4.14	ACCEPTED BY